

**Microzone Corporation Acid Hood
Clean Air Type Specification**

PART 1 GENERAL

PART 1.01 GENERAL INFORMATION

This Section specifies all requirements necessary to furnish and install a horizontal laminar flow exhausted acid work station including, but not limited to the following:

1. This specification covers the requirements for a Class 100 (ISO Class 5) as per federal standard 209, horizontal laminar flow exhausted acid work station.
2. Nominal 4,5 and 6-foot widths are covered by this specification.
3. This specification sets the intent for quality, performance and appearance.
4. Supply and install as scheduled in laboratory schedule and drawings.
5. Coordinate installation with other trades to avoid onsite conflicts.
6. Reference related sections within the specification document in conjunction with the following specifications to insure total requirements for the referenced horizontal laminar flow exhausted all polypropylene acid work stations are provided.

1.02 QUALITY ASSURANCE

1. The manufacturer shall maintain a testing facility at their place of business for the performance testing of laminar flow work stations. Both laminar flow work stations and installation shall be in conformance to good construction practice and approved by the owner/user. The test facility as well as the manufacturing facility must be available for owner/user inspection and its quality control procedures. All work stations to be wired for 115 volts, 60 Hz shall be built to meet or exceed the minimum requirements of federal standard 209, CLASS 100(ISO Class 5)

1.03 REFERENCES

1. The horizontal laminar flow exhausted acid work stations shall conform to the following regulations and standards:
Federal Standard 209 and ISO-14644-1

1.04 SUBMITTALS

1. Horizontal laminar flow exhausted acid work station specification sheets and product manuals shall be submitted by the manufacturer upon request. The work station supplier shall submit shop drawings when necessary for clarification.
2. Provide a detailed copy of the test results conducted prior to shipping to ensure compliance with Federal Standard 209 shall be shipped with each cabinet.

1.05 DELIVERY AND STORAGE

1. Horizontal laminar flow exhausted acid work stations shall be delivered in unopened crated packages adequately protected from damage during shipment.
2. Exercise extreme care in handling all work stations to prevent any damage.
3. Store materials within the building in the space designated for storage. Store materials in such manner as to prevent any damage or intrusion of foreign matter. Any damaged materials must be noted and scheduled with the job site installation foreman for removal and replacement from the job-site prior to installation.

1.06 WARRANTY

1. Manufacturer's warranty against defects in material or workmanship on its work stations for 1 year from date of shipping, shall include replacement of parts (except prefilters, HEPA or ULPA filters and lamps) and labor. The cabinet supplier shall not be responsible for or liable for any modifications, alterations, misapplication or repairs made to the products in the field after product final installation.

"Simply Building Better Environments For Advanced Technology & Life Sciences"

Microzone Corporation, 86 Harry Douglas Drive, Ottawa, Ontario, Canada K2S 2C7

Telephone: (613) 831-8318 Toll Free: (877) 252-7710 Fax: (613) 831-8321

Email: sales@microzone.com Web Site: www.microzone.com

**Microzone Corporation Acid Hood
Clean Air Type Specification**

PART 2 - PRODUCTS

2.01 PRODUCT NAME

Horizontal Laminar Flow Exhausted Acid Work Stations, All Polypropylene Type, model numbers as described below:

4 Foot Models: AH-4-99, 5 Foot Models: AH-5-99, 6 Foot Models: AH-6-99,

2.02 ACCEPTABLE MANUFACTURER

Microzone Corporation,
Laboratory Equipment Group,
86 Harry Douglas Drive,
Ottawa, Ontario, Canada, K2S 2C7
Phone: 613-831-8318, or Toll Free: 1-877-252-7710
Fax: 613-831-8321, Email: sales@microzone.com

2.03 MATERIALS OF CONSTRUCTION

1. Interior construction shall include walls constructed from white polypropylene. The solid work surface with integral pot sink and containment lip shall also be constructed from white polypropylene.
2. Exterior panels shall be constructed from white polypropylene without exposed bolts or nuts.
3. Exhaust plenum shall be integral and constructed from white polypropylene, terminating in a duct collar connection flange.
4. HEPA filters shall be a minimum of 99.99% efficient on all particles 0.3µm. HEPA filters shall be industry-standard size metal-free separatorless type.
5. Fluorescent lighting shall provide 80 to 100 foot-candles on work surface sealed in a clear P.V.C. shroud.
6. The recessed horizontal sliding sash shall include thick clear P.V.C. faceshield enclosed in a white polypropylene frame. All sash mechanisms shall be none-metal and located in a front easy access service chase.
7. White polypropylene 5" X 9" X 6" integral drop-in sink module with bottom drain and polypropylene D.I. water gooseneck faucet with remote operator.
8. Speed control shall be solid state and load rated for motor voltage and shall be set and adjusted electronically.
9. Electronic "SPM" constant pressure gauge shall monitor system pressure. This system reports the static condition of the integral filter systems both visual and audible with an alarm feature in the event of drop in static, motor failure or increased pressure.
10. Motor shall be maintenance free, permanently lubricated ball bearing armature motor with single inlet centrifugal fan.
11. Integral vented polypropylene storage section complete with horizontal sliding access doors and single adjustable shelf.
12. All services factory plumbed and wired for single point field connection.
13. Digital "DMC" soft start circuit motor control panel with on/off feature for blower/white and ultraviolet light switch and interior duplex outlet. Integral circuitry provides constant monitoring of voltage to the motor, current motor draw, line voltage frequency and on-board diagnostics. In the event of a system fault, the system features flash codes on LED display indicating area of failure.
14. Electronic "AFI-X2" airflow alarm gauge shall monitor system exhaust airflow. This system reports the static condition of the unit's exhaust airflow providing both visual and audible alarms signaling a problem with the building exhaust fan or increased static pressure.

"Simply Building Better Environments For Advanced Technology & Life Sciences"

Microzone Corporation, 86 Harry Douglas Drive, Ottawa, Ontario, Canada K2S 2C7
Telephone: (613) 831-8318 Toll Free: (877) 252-7710 Fax: (613) 831-8321
Email: sales@microzone.com Web Site: www.microzone.com

**Microzone Corporation Acid Hood
Clean Air Type Specification**

15. HEPAIRE patented internal air plenum.

2.04 FABRICATION

1. Overall exterior dimensional information on Horizontal Laminar Flow Exhausted All Polypropylene Acid Work Stations is as described in the table.
Nominal Dimensions
4 ft. Model: 56" w x 30" d x 96" h, 5 ft. Model: 66" w x 30" d x 96" h
6 ft. Model: 78" w x 30" d x 96" h
2. The exterior shell shall be constructed from white polypropylene, with continuous seam welded construction complete with a removable front access panel with sufficient structural reinforcement to provide a rigid, stable unit.
3. The interior shell shall be constructed from white polypropylene, with dual removable side access service panels.
4. Provide a full width and depth solid work surface with integral containment lip on a integral vented polypropylene storage section complete with horizontal sliding access doors and single adjustable shelf.
5. Provide full depth integral exhaust plenum from the side, exhausting one side of the work surface. The air intake airflow slots, located in front of the cabinets inflow grille, shall draw laboratory air directly into the cabinet through the primary stage pre-filtration (40%) then through the final HEPA filter down in a horizontal airflow plenum directly to the clean side of the work surface.
6. Cabinet assembly shall be constructed such that all positive pressure plenums shall be all sealed, with all cabinet major service operations performed from the front of the cabinet.
7. Supply metal free HEPA filters rated 99.99% efficient on all particles 0.3µm shall be secured in the upper cabinet assembly by filter hold down frame clamped. HEPA filters shall be removable from the front of the cabinet.
8. Sash shall be recessed and horizontal sliding, capable of moving to a fully opened position when cabinet is not in operation. Sash shall not require removal for routine filter or motor/blower service.
9. All major electronic components (speed control, ballasts, starters, switches, motor capacitors, circuit breakers) shall be housed in a removable module for service or testing, located in the front valence of the cabinet.
10. The fully electronic soft touch "DMC" digital motor control keypad with on/off indicators on all switches and feature dual processor controls, LVS(Low Voltage Stabilization) circuitry and calibrated linear static pressure display (LED's) complete with high/low audio and visual alarm feature and mute function shall be mounted on the front face of the cabinet.
11. The "SPM" static pressure gauge complete with audio/visual and mute functions shall be mounted on the front face of the cabinet for easy visibility and shall be connected to a positive pressure duct.
12. Motor mounting system shall be a permanent part of the motor housing.
13. The cabinet shall be pre-wired terminating in an electrical service outlet located on the rear base section ready for connection to a suitable 115 volt service.
14. No exposed metal downstream of the final HEPA filter.
15. Integral service utilities including, two acid resistant switched duplexes, one air, gas and vacuum outlet with remote operators. All terminations located within base cabinet.

"Simply Building Better Environments For Advanced Technology & Life Sciences"

Microzone Corporation, 86 Harry Douglas Drive, Ottawa, Ontario, Canada K2S 2C7

Telephone: (613) 831-8318 Toll Free: (877) 252-7710 Fax: (613) 831-8321

Email: sales@microzone.com Web Site: www.microzone.com

PART 3 - EXECUTION

3.01 INSPECTION

1. Carefully check the contents of the carton for damage that might have occurred in transit.

3.02 PREPERATION

1. Verify equipment rough in before proceeding with work.
2. Coordinate with other trades for the proper and correct installation of plumbing and electrical rough in and for rough opening dimensions required for the installation of the hood.

3.03 INSTALLATION

1. Install according to manufacturer's instructions.
2. Install according to standards required by authority having jurisdiction.
3. Install equipment plumb, square and straight with no distortion and securely anchor as required.
4. Sequence installation to ensure utility connections are achieved in an orderly and expeditious manner.
5. Touch up minor damaged surfaces caused by installation. Replace damaged components as directed by Architect.

3.04 FIELD QUALITY CONTROL

1. A qualified independent certifier should certify the cabinet before use. The certifier should perform tests as recommended in the manual.

3.05 CLEANING

1. Clean equipment surfaces as recommended by the manufacturer, rendering all work in a new and unused appearance.
2. Clean adjacent construction and surfaces, which may have been soiled in the course of installation of work in this section.

3.06 PROTECTION

1. Provide all necessary protective measures to prevent exposure of equipment and surfaces from exposure to other construction activity.
2. Advise contractor of procedures and precautions for protection of material from damage by work of other trades.

"Simply Building Better Environments For Advanced Technology & Life Sciences"

Microzone Corporation, 86 Harry Douglas Drive, Ottawa, Ontario, Canada K2S 2C7

Telephone: (613) 831-8318 Toll Free: (877) 252-7710 Fax: (613) 831-8321

Email: sales@microzone.com Web Site: www.microzone.com